

# BRUHAT BANGALORE MAHANAGARA PALIKE


BBMP/2014-15/OW/WORK\_INDENT13881/CALL-1

## APPROVED SCHEDULE - B

Tender Notification EE/BTP/BBMP/E-PMT/08/2014-15, Date: 30.12.2014

**Maintenance of Ward and Emergency Works in Ward No. 11 (Kuvempunagara), Vidyaranyapura Sub Division.**

| Sl. No. | Approved Qty. | Description                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                            | Unit | Approved Tender Rates of |                                                                           |
|---------|---------------|------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|------|--------------------------|---------------------------------------------------------------------------|
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | CHETHAN C                |                                                                           |
|         |               |                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                        |      | In Figures               | In Words                                                                  |
| 1       | 24.84         | Earth work excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                          | Cum  | 105.0                    | Rupees One Hundred Five Only                                              |
| 2       | 3.24          | Providing and laying in position plain cement concrete of mix 1:4:8 with OPC cement @ 180 kgs with 40mm and down size graded granite metal coarse aggregates @ 0.85cum and fine aggregates @ 0.57 cum machine mixed, concrete laid in layers not, exceeding 15cms, thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                              | Cum  | 4847.0                   | Rupees Four Thousand Eight Hundred Forty Seven Only                       |
| 3       | 34.56         | Providing and constructing granite / trap / basalt size stone masonry in superstructure with cement mortar 1:6, edges of stones chistle dressed in courses not less than 15 cms high, bond stones at two m. apart in each course including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                       | Cum  | 4773.6                   | Rupees Four Thousand Seven Hundred Seventy Three and Sixty Paise Only     |
| 4       | 51.2          | Providing ruled pointing to coursed stone masonry with cement mortar 1:4, 20 mm deep, after raking joints to depth of 20mm nicely lining, including cost of materials, labour, curing etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                                              | Sqm  | 92.88                    | Rupees Ninety Two and Eighty Eight Paise Only                             |
| 5       | 7.8           | Providing and laying in position plain cement concrete of mix 1:2:4 with cement @ 240 kgs with 20mm and down size graded granite metal coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum, machine mixed, concrete laid in layers not exceeding 15cms, thick, well compacted, in foundation, plinth and cills, including cost of all materials, labour, HOM of machinery, curing etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                                                                        | Cum  | 5327.64                  | Rupees Five Thousand Three Hundred Twenty Seven and Sixty Four Paise Only |
| 6       | 23.15         | Providing and laying in position reinforced cement concrete of design mix M20 with OPC cement @ 320 kgs, with 20mm and down size graded granite metal, coarse aggregates @ 0.878 cum and fine aggregates @ 0.459 cum with superplastisiser @ 3lts conforming to IS 9103-1999 reaffirmed-2008 machine mixed, concrete laid in layers not exceeding 15cms thick, vibrated for all works in foundation plinth and ground floor level for roof slabs, staircase, lintels, retaining walls, walls (any thickness) including attached plasters, column, piers, abutments, pillars, posts, struts, buttresses, string or lacing courses, parapets, coping, bed blocks, anchor blocks, plain window cills, fillets etc, including cost of all materials, labour, HOM of machinery, curing, etc complete as per specifications and directions of engineer in charge of the work | Cum  | 6065.0                   | Rupees Six Thousand Sixty Five Only                                       |

  
**Executive Engineer**  
 Byataranyapura Division  
 Yelahanka Zone  
 Bangalore - 1

|    |       |                                                                                                                                                                                                                                                                                                                                                                                                                                                                          |     |        |                                                          |
|----|-------|--------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------------|-----|--------|----------------------------------------------------------|
| 7  | 18.52 | Providing mild steel reinforcement for R.C.C work including straightening, cutting, bending, hooking, placing in position, lapping and / or welding wherever required, tying with binding wire and anchoring to the adjoining members wherever necessary complete as per design (laps, hooks and wastage shall not be measured and paid) cost of materials, labour, HOM of machinery etc complete as per specifications and directions of engineer in charge of the work | Qtl | 7970.0 | Rupees Seven Thousand Nine Hundred Seventy Only          |
| 8  | 92.38 | Providing and removing centering, shuttering, strutting, propping etc., and removal of form work for vertical surface such as walls at any thickness, including attached pilasters, buttresses, plinth and string courses cost of all materials, labour etc complete as per specifications and directions of engineer in charge of the work                                                                                                                              | Sqm | 292.68 | Rupees Two Hundred Ninety Two and Sixty Eight Paise Only |
| 9  | 20    | 1031 - Hire Charges of J.C.B Excavator including Operator and Fuel (P. XXXXVI/I. 23) etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                 | Day | 6720.0 | Rupees Six Thousand Seven Hundred Twenty Only            |
| 10 | 70    | 1024 - Hire Charges of Tractor 40 HP including Operator and Fuel (P. XXXXVII/I. 19) etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                  | Day | 2240.0 | Rupees Two Thousand Two Hundred Forty Only               |
| 11 | 700   | Engaging Casual Labours (Unskilled mazdoor Heavy) etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                                                                                    | Nos | 223.0  | Rupees Two Hundred Twenty Three Only                     |
| 12 | 23.6  | Lead for Disposal of Debris shall be payable at carriage rates by Mechanical means including loading and unloading etc complete as per specifications and directions of engineer in charge of the work                                                                                                                                                                                                                                                                   | Cum | 73.0   | Rupees Seventy Three Only                                |

  
Signature of the Contractor

  
Executive Engineer  
Byarayanapura Division  
BBMP, Bangalore - 92